

Official Notice
Advertisement for Bids
Culvert Replacement, Asphalt pulverizing, Gravel Base & Shaping

Pursuant to Wisconsin State Statute Chapter 985, notice is hereby given that the Town of Sumner Barron County, Wisconsin, will receive sealed bids for the following project until 7:00 p.m. local time on Tuesday, September 10, 2024). Bids should be submitted to the Town of Sumner Clerk: 1550 24½ St, Rice Lake WI 54868-8725. Please mark the envelope “Bid for Culvert Replacement, Asphalt pulverizing, Gravel Base & Shaping.” Project materials will be posted on the town’s website at <https://www.townofsumner-wi.com>. Contact the Town at 715-859-6250 or clerk@tn.sumner.wi.gov with any project related questions. Bids will be publicly opened at the Town Board meeting that starts at 7:00 p.m. September 10, 2024 at the Sumner Town Hall, 1550 24½ ST/Barron CO Hwy M, Rice Lake, WI, just north of Canton. This is LRIP/TRIS project #18671.

OLD 14 PROJECT LOCATION: 15 1/2-16Th Ave. beginning at Barron Co Hwy M north of Canton heading east approximately 2.56 miles (13,540 feet) ending at 27th St.

PROJECT DESCRIPTION

- Furnish and install four (4) aluminized steel culverts, 3 each 36"x 46' & 1 each 24"x 46'. Culvert installation shall include pavement removal, excavation, bedding and granular backfill compacted to existing subgrade elevation. Base reinstatement to pavement grade paid separately.
- Remove and replace road subbase in low or sunken road areas marked (A) 60'x24' & (B) 85'x24'. Remove 20" in depth below existing road surface and replace with 12 inch compacted thickness of 3" Dense Graded Base over MIRAFI HP370 geotextile fabric or equal. Reinstatement road base with 8 inch compacted thickness of 1-1/4" Dense Graded Base. Contractor shall provide offsite disposal of excavated materials.
- Pulverize existing asphalt surface. After pulverizing, shaping & compacting, Place a 2.5 inch nominal compacted thickness of 1-1/4" Dense Graded Base over the reshaped surface. The blend of pulverized pavement and base shall be graded and compacted to a 24-foot width with a normal 2% centerline crown.

Estimated bid quantities are as follows:

Item No.	Description	Units	Quantity	Unit Price
	Pulverize and Re-grade Existing Pavement	SY	30,100	
	Subbase Excavation & Disposal	CY	220	
	Geotextile Fabric	SY	390	
	36"x46' Aluminized Steel Culvert	Each	3	
	24"x46' Aluminized Steel Culvert	Each	1	
	3" Dense Graded Base	Ton	260	
	1-1/4"Dense Graded Base	Ton	4,100	

The work schedule shall be as proposed by the Bidder, but shall be completed no later than Dec.31 2024. *The final schedule will be mutually agreed to by the Town of Sumner and the Successful bidder.*

The Bidder's unit price bid shall include all costs associated with producing, hauling, and placing the material including, but not limited to, mobilizing and demobilizing labor and equipment required to produce, haul, and place the material; costs of quality control testing and reporting; costs to produce the material to the specifications; traffic control; costs of permitting, licensing, and reporting as required; all overhead, profit and administrative costs; and any other incidental items required for the work as specified. The work shall be completed in accordance with the latest edition of the Wisconsin Department of Transportation Standard Specifications for Road and Bridge Construction. The Town of Sumner reserves the right to reject any and all bids and to waive any informality in the bidding process or accepting bids which best serves the interest of the Town.